

To,
 Canara robeco AMC Ltd.
 4th floor, Construction House,
 5, Walchand Hirachand Marg,
 Ballard Estate, Mumbai - 400 001.

Date: 30 July 2015

| Sub: Quotation for the interior renovation work to be done at Patna Branch Office of Canara Robeco. | | | | | |
|--|---|------------|-------------|-------------|-------------|
| No | Item Description | Qty | Unit | Rate | Cost |
| A Pantry Works | | | | | |
| 1 | Aluminium Glazed partition with door | 35.00 | sft | | |
| B Working area/Meeting Room | | | | | |
| 1 | 12m thick toughened Glass partition with door all with patch fitting | 25.00 | sft | | |
| 2 | Laminated Running counter made out of 19mm thick block board with drawers and shutters of lock and key arrangement. The dept of the counter being 600mm | 15.00 | rft | | |
| 3 | Low Height wooden partition with our of wooden frame work of 50mmx50mm with 6mm ply on woth sides finished with 1mm laminate | 60.00 | sft | | |
| 4 | Pin Up Boards made out of salotex board finished with cloth of approved shade | 24.00 | sft | | |
| 5 | Laminated cupboards made out of 19mm thick block board with lock and key arragement for shutters | 15.00 | sft | | |
| 6 | P/f laminated base and glass top ellipse shaped conference room table | 1.00 | job | | |
| 7 | Providing and fixing Polished brochure / Magazine Stand | 1.00 | job | | |
| C Electrical / Data / Voice Cabling | | | | | |
| 1 | Wiring with CAT 6 Cable including termination with RJ45 connector | 8.00 | no | | |
| 2 | 2m patch cord | 8.00 | no | | |
| 3 | 1m Patch cord | 8.00 | no | | |
| 4 | 9U Hub Rack | 1.00 | no | | |
| 5 | 24 port Jack panel | 1.00 | no | | |
| 6 | 24port switch | 1.00 | no | | |
| 7 | Wiring for telephone points with 2 pair telephone cable complete with RJ11 connectors | 7.00 | no | | |
| 8 | Wiring for UPS points with 2x2.5 sqmm PVC insulated copper conductor wire | 16.00 | no | | |
| 9 | Wiring with 2x2.5sqmm PVC insulated copper conductor wire for RAW Power. Including Anchor ROMA switch plate and switches | 8.00 | no | | |

| | | | | | |
|----|--|--------------------|-----|-------------|--|
| 10 | Distibution Board for UPS | 1.00 | no | | |
| 11 | Copper plate earthing (Rate Only) | 0.00 | no | | |
| 12 | Wiring with 1x10 sqmm as earth connector | 15.00 | rmt | | |
| 13 | wall fans | 4.00 | no | | |
| | | | | | |
| | | Total | | 0.00 | |
| | | Add VAT @ 12.5%(on | | | |
| | | Add ST@ 14%(on | | | |
| | | Grand Total | | 0.00 | |